



Dąbrowa Górnicza, 14.12.2020

Answers to questions received during the tender process no. 1/0099_18/2020

Regarding the request for quotation no. 1/0099_18/2020 concerning **purchase, deliveries (in accordance with DDP INCOTERMS 2010), installation and start-up of the pilot installation of the gas cleaning plant for Blast Furnace No. 2 in Dąbrowa Górnicza.**

QUESTION	ANSWER
1. Question to Appendix 10 to the technical specification "Battery limits" - 13. Electrical supply	Please assume that the location of the 6kV and 0.4kV switching room (S-107 / T-107) complies with the map in Annex 10, point 13 and is located in the AKP BF2 building. Any currently missing power sources will be adjusted by AMP up to the switching room in the AKP building. Estimated length of cabling is 150 meters in open cable trays.
2. Question to technical specification 6.1 point 4 regarding expected noise level	Requirement refers to noise level measured in the perimeter of new cyclone and scrubber installation.